



2015000333Z



(2015)国认监认字(077)号



中国认可
国际互认
检测
TESTING
CNAS L0230

检 验 报 告

TEST REPORT

BETC-KJ-2017-10


工程 / 产品名称
Name of Engineering / Product 液压自爬模

委托单位
Client 苏州拓恒建筑科技有限公司 (良工)

检验类别
Test Category 委托检验

国家建筑工程质量监督检验中心

NATIONAL CENTER FOR QUALITY SUPERVISION
AND TEST OF BUILDING ENGINEERING



注 意 事 项

NOTICE

1. 报告无“检验鉴定章”或检验单位公章无效；

Test report is invalid without the “Stamp of test report” or that of test department on it.

2. 复制报告未重新加盖“检验鉴定章”或检验单位公章无效；

Duplication of test report is invalid without the “Stamp of test report” or that of test department re-stamped on it.

3. 报告无主检、审核、批准签字无效（仲裁检验报告应增加审定签字）；

Test report is invalid Without the signatures of the persons for chief test, verification and approval. The test report for arbitration should be added the signature of the person for verification on it.

4. 报告涂改无效；

Test report is invalid if altered.

5. 对检验报告若有异议，应于收到报告之日起十五日内向检验单位提出；

Different opinions about test report should be reported to the test department within 15 days from the date of receiving the test report.

6. 一般情况，委托检验仅对来样负责，样品信息由委托方提供。

In general, for entrusted tests the responsibilities are undertaken for the delivered samples only and the sample information is provided by clients.

地址：北京市朝阳区北三环东路30号

ADD: NO.30, Beisanhuan East Road, Chaoyang District, Beijing, China

电话(Tel)：010-84281338 010-64517787

投诉电话：010-64517830

传真(Fax)：010-84288515 010-84281338

邮政编码(Post code)：100013

Internet: <http://www.cabr-betc.com>

国家建筑工程质量监督检验中心检验报告

TEST REPORT OF NATIONAL CENTER FOR QUALITY SUPERVISION AND TEST OF BUILDING ENGINEERING

报告编号 (No. of Report) : BETC-KJ-2017-10

共 7 页第 1 页 (Page 1 of 7)

委托单位 (Client)		苏州拓恒建筑科技有限公司/ Suzhou TECON Construction Technology Co, Ltd			
地 址 (ADD)		南京市建邺区奥体大街 69 号新城科技大厦 01 栋 20 层 20F/L, Building 1, Xincheng Science & Technology Mansion, No.69, Aoti Street, Jianye District, Nanjing City, Jiangsu Province, China			
样品 Sample	名称 (Name)	液压自爬模/ Hydraulic Self climbing formwork		商标 (Brand)	LIANGGONG
	规格型号 (Type/ Model)	LG-120		编号 (No.)	KJ-2017-10
	数量 (Quantity)	两机位/Two Hydraulic climbers		状态 (State)	正常/ Normal
生产单位 (Manufacturer)		江苏良工建筑模板有限公司 / Jiangsu Lianggong construction formwork Co.Ltd			
检验 (Test)	项目 (Item)	架体结构应力、主操作台悬挑和跨中挠度、同步性能/Stress in the frame structure, Deflection at cantilevered span and mid-span of main operating platform, Synchronization performance			
	地点 (Place)	委托单位设备基地/ Equipment base of client		日期 (Date)	2017/01/19
	仪器 (Instruments)	应变仪、经纬仪等/ Strain gauge, Theodolite ect.			
检验依据 (Test based on)		JGJ 195-2010, JGJ 202-2010			
判定依据 (Criteria based on)		JGJ 195-2010, JGJ 202-2010			
检验结论 (Conclusion)					
<p>经检验:</p> <ol style="list-style-type: none"> 1. 额载使用工况所测最大结构应力值+45.44 N/mm² (测点 4); 2. 超载使用工况所测最大结构应力值+54.30 N/mm² (测点 4); 3. 爬升工况所测最大结构应力值+26.49 N/mm² (测点 10); 4. 额载使用工况主操作平台挠度最大值 14 mm。 <p>结论: 该液压自爬模 (两机位) 所测最大结构应力值小于所用材料设计应力; 同步性能检验结果符合检验标准要求。</p> <p>Conclusion: For this hydraulic self-climbing formwork, the maximum structural stress value is less than the design value of the material used. The test result of the synchronous performance test meets the requirements of the inspection standard.</p> <p>(本页以下无正文) (There is no text below this page)</p>					
批准 (Approval)	审核 (Verification)	主检 (Chief tester)	联系电话 (Tel)	报告日期 (Date)	
			(0316) 2023837 (0316) 2311488	2017/05/22	